

BRUHAT BANGALORE MAHANAGARA PALIKE

Name of work : Development of parks in ward no.4 Yelahanka New town

Development of parks in ward no.4 Telanarika New town							Est cost : Rs 100.00 lakhs		
Sl. No.	Description of work	Unit	No.	Length	Breadth	Depth	Quantity	Rate in Rs.	Amount in Rs.
				m	m	m			
1	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 (P.No.6, I.No.2.3 of PW, P&IWTD SR 2018-19)								
	Park	Cum							
	Open gym equipment area		3	44.00	0.30	0.20	7.92		
	Children's play area		1	60.00	0.30	0.20	3.60		
							11.52	316.94	3651.15
	Basic rate	299.00							
	Area Weightage 6%	17.94							
	Final Rate	316.94							
2	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggretes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No-13,I No-4.6)								
	Park	Cum							
	Open gym equipment area		3	44.00	0.30	0.15	5.94		
	Children's play area		1	60.00	0.30	0.15	2.70		
							8.64	5747.32	49656.84
	Basic rate	5422.00							
	Area Weightage 6%	325.32							
	Final Rate	5747.32							
3	KSRRB M300-53. Construction of embankment with approved material Gravel/Murum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murum, watering charges & compaction by vibratory roller to 95% of modified proctors density. MORTH Specification No. 305 (P.No.147, I.No.19.60 of PW,P&IWTD S.R 2018-19)								
	Park	Cum							
	Open gym equipment area		3	10.00	12.00	0.20	72.00		
							72.00	344.50	24804.00
	Basic rate	325.00							
	Area Weightage 6%	19.50							
	Final Rate	344.50							
4	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No. 13/I.No. 4.2 of CSR 2018-19)								
	Park	Cum							
	Open gym equipment area		3	10.00	12.00	0.15	54.00		

No.	Description of work	Unit	No.	Length	Breadth	Depth	Quantity	Rate in Rs.	Amount
				m	m	m			
	Basic rate	5194.00					54.00	5505.64	29
	Area Weightage 6%	311.64							
	Final Rate	5505.64							
5	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification. (P.No. 112, I.No. 14.62 of PWD SR 2018-19)								
	Open gym equipment area		3	10.00	12.00		360.00		
	Basic rate	Sqm					360.00	1305.92	47013
	Area Weightage 6%	1232.00							
	Final Rate	73.92							
		1305.92							
6	KSRB 14.6 : Providing and laying heavy duty cobble stones interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM complete as per specifications. Specification No. KBS (P.103/I.14.6) PWD SR 2018-19, 60mm thick								
	Park pathway		1	250.00	1.60		400.00		
	Basic rate	Sqm					400.00	1116.18	446472.0
	Area Weightage 6%	1053.00							
	Final Rate	63.18							
		1116.18							
7	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc., complete. As per the direction of Engineer incharge. (P.No.27, I.No.5.30 of PW, P&IWTD SR 2018-19)								
	Park pathway		2	250.00			500.00		
	Open gym equipment area		3	44.00			132.00		
	Children's play area		1	60.00			60.00		
		Nos					692.00		
	Basic rate	408.00					1538.00	432.48	665154.24
	Area Weightage 6%	24.48							
	Final Rate	432.48	0.45						
8	KSRB 15-18.3 : Providing and applying enamel metal paint one coat (excluding priming coat) on previously painted steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. (P.No.123, I.No.15.75 of PW, P&IWTD SR 2018-								
	Park pathway		2	250.00		0.40	200.00		
	Open gym equipment area		3	44.00		0.40	52.80		
	Children's play area		1	60.00		0.40	24.00		
	Basic rate	Sqm					276.80	64.66	17897.89
		61.00							

Sl. No.	Description of work	Unit	No.	Length m	Breadth m	Depth m	Quantity	Rate in Rs.	Amount in Rs.
	Area Weightage 6%	3.66							
	Final Rate	64.66							
9	KSRRB M1200-46. Sand filling in wells complete as per drawing and technical specifications including cost of all materials, labour, HOM, form works, scaffolding & centering complete as per specifications. MORTH Specification No.1207 (P.No.217, L.No.26.124 of PW, P&IWTDR SR 2018-19)								
	Children's play area		1	15.00	15.00	0.30	67.50		
		Cum					67.50	2806.88	189464.40
	Basic rate	2648.00							
	Area Weightage 6%	158.88							
	Final Rate	2806.88							
10	Supply and Fixing of Pull Down Challenger. Metal: All tubular steel of 2 .5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All weld d joints are scalloped as necessary and welded to an approved MIG process.All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at ll the welding points prior to finishing . All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. Allmetal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to 1507227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for th e handles. Bearings:Maintenance-free ball bearings. Scope of delivery: 1completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified internat ional certifying agency such as IPEMA,TUV,CPSC, or SGS only.The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must clearly display the GS ma rk as has been issued in the EN16630 safety certificates. Size L x W x H): 2570 x 805 x 2685 mm. Weight: 85.4 Kg Safety Area : 6287 x 4858 mm								
		Each	3				3.00		
							3.00	240000.00	720000.00
	Data Rate	240000							
11	Supply and fixing of Seated Chest Press. Metal: All tubular steel of 2.5mm thikness are galvanized and z inc dipped. Joints are Robotic welded. All welded joints t1H • scalloped as necessary and welded to an approved MIG process. All welds an• 111 cased off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the w 11lt1ing points prior to finishing. All metal parts are powder coated using AKZO Nobel (11 ca t Wall powder to the thickness of 80-120 microns. All metal parts are tested in rn 1r a lt spray machine that uses a 5% NaCl solution in accordance to 1507227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handle!,,Bearings: Maintenance-free ball bearings. Scope of delivery: 1completely Prt' ,ssembled equipment modules. Maintenance: Maintain according to EN 166630 and the maintenance guide. Safety: All products must be tested and certified to mt•(•EN16630 safety standards with GS test mark. The EN 16630,certificates must be issued by a reputed notified international certifying agency such as IPEMA, 1UV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party.All products must clearly display the GS inark as has been issued in the EN16630 safety certificates. All products must carry n GS mark :in it.. Size L x W x H):								
		Each	3				3.00		
							3.00	230000.00	690000.00
	Data Rate	230000							

Sl. No.	Description of work	Unit	No.	Length	Breadth	Depth	Quantity	Rate in Rs.	Amount in Rs.
				m	m	m			
12	Supply and fixing of Self Weighted Rower. Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Colour RAL 5019 Blue and RAL 1014 Beige Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules. Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards only by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS. The GS Mark-EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must carry a GS mark on it. Size L x W x H: 1390 x 805 x 1100 mm. Weight: 42.4 Kg Safety Area: 3790 x 3205 mm Capacity_1 Person.	Each	3				3.00		
							3.00	165000.00	495000.00
	Data Rate	165000							
13	Supply and fixing of Elliptical Cross Trainer. Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS only. The GS Mark-EN16630 Certificates must be in the name of tendering party and not any 3rd party. The certificates must be attached with the tender document. All products must clearly display the GS mark as has been used in the EN16630 safety certificates. Size L x W x H: 1267 x 582 x 1764 mm. Weight: 43.5 Kg Safety Area: 4322 x 3632 mm	Each	3				3.00		
							3.00	140000.00	420000.00
	Data Rate	140000							

Sl. No.	Description of work	Unit	No.	Length	Breadth	Depth	Quantity	Rate in Rs.	Amount in Rs.
				m	m	m			
14	Supply and Fixing of Rider. Metal: All tubular steel of 2.smm thickness are galvd 1 ilzed and zinc dipped . Joints are Robotic welded. All weldect joints are scalloped as necessary and welded to an approved MIG proi;ess. .<\11 welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing.All metal parts are powder Clated using AKZO Nobel-G reat Wall powder to the thickness of 80-120 microns. All Il\etal parts are tested in our sa lt spray machine that uses a 5% NaCl solution in accorcJ<ince to 1507227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubher is used for the handles. 5 Bearings : Maintenance-free ball bearings...Scope of c:l livery: 1completely pre-assembled equipment modules. Maintenance: Maint<lin according to EN 16630 a nd the maintenance guide. Safety: Alf products must b tested and certified to meet EN16630 safety standards with GS test mark. The El\! 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV ,CPSC, or SGS only. The GS Mark-EN16630 Certificate must be in the name of tendering party and not any 3rd party. All products 'hust clearly display the GS mark as has been issued in the EN 16630 safety certificat . Size L x w x H): 910 x 655 x 1270 mm. Weight : 29.5 Kg Safety Area: 3310 x tnm C;pacity_ l								
		Each	3				3.00		
							3.00	90000.00	270000.00
	Data Rate	90000							
15	Supply and Fixing of Bicycle. Metal: All tubular steel of 25mm thickness are galvani zed and zinc dipped. Joints are Robotic welded. All welded joint s are S('.liloped as necessary and w eldea to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the weltling points prior to finishing.All metal parts are powder coated using AKZO Nobel GreatWall powder to the thickness of 80- 120 microns. All metal parts are tested in our salt v pray machine that uses a 5% NaCl solution in accordance to IS07227 to speed up -orrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. each 1 125000 125000 131188 131188 134500 134500 Bearings: Maintenance-free ball bearings . Scope of delivery: 1completely pre assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to mee t EN16630 safety standards only by a reputed notified international certifying acency such as IPEMA,TUV,CPSC, or SGS. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. Size_L x W x H): 1000 x 498 x 120 mm. Weight : 51.5 Kg Safety Area: 3400 x 3498 mm Capacity l Persons.								
		Each	3				3.00		
							3.00	125000.00	375000.00
	Data Rate	125000							
16	Supply and Fixing of Arm & Pedal Bike. Metal: All tubular steel of 2.Smm thickness a re galvanized and zinc dipped.Joints are Robotic welded.All welded joints are sca lloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to IS07227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles.Bearings : Maintenance-free ball bearings.Scope of delivery: 1completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide.Safety : All products must be tested anEl certified to meet EN16630 safety standards only by a reputed notified international certifying agencv such as IPEMA,TUV, CPSC, or SGS. The GS Mark- EN16630 Certificates must be in t he name of tendering party and not any 3rd party.Size_ L x W x H): 830 x 500 x 1450 mm. Weight: 32 Kg Safety Area: 3830 x 2900 mm								
		Each	3				3.00		
							3.00	170000.00	510000.00


Sl. No.	Description of work	Unit	No.	Length	Breadth	Depth	Quantity	Rate in Rs.	Amount in Rs.
				m	m	m			
	Data Rate	170000							
17	Supply and fixing of Twist Stepper. Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-GreatWall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. Size_ L x W x H): 1395 x 650 x 1750 mm. Weight: 53.8 Kg Safety Area.: 3795 x 3050 mm Capacity_2 Persons.								
		Each	3				3.00		
							3.00	180000.00	540000.00
	Data Rate	180000							
18	Supply and fixing of HD Health Walker. Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Colour RAL 5019 Blue and RAL 1014 Beige Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings. 11 Scope of delivery: 1 completely pre-assembled equipment modules. Maintenance: Maintain according to EQ and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. The certificates must be attached with the tender document. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. Size (L x W x H): 1065 x 615 x 1364 mm. Weight: 51Kg. Safety Area: 4090 • 3555mm. Capacity 1 Person								
		Each	3				3.00		
							3.00	140000.00	420000.00
	Data Rate	140000							


Sl. No.	Description of work	Unit	No.	Length	Breadth	Depth	Quantity	Rate in Rs.	Amount in Rs.
				m	m	m			
19	Supply and fixing of HD Squat Pushing. Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are sanded as necessary: and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. Size L x W x H: 2270 x 635 x 1640 mm. Weight: 60.2Kg. Safety Area: 5300 * 3685mm. Capacity 2 Persons	Each	3				3.00		
	Data Rate	215000					3.00	215000.00	645000.00
20	Supply and fixing of HD Waist Twister. Metal: All tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are sanded as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to ISO7227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings. Scope of delivery: 1 completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. Size L x W x H: 1460 x 1310 x 450 mm. Weight: 39.1 Kg. Safety Area: 4360 x 4510 mm	Each	3				3.00		
	Data Rate	130000					3.00	130000.00	390000.00
21	Providing, fabricating and fixing Special Multiplay Systems consists of FRP moulded with Aluminium chequered platforms of size 5x5 ft with 4 support pillar made out of 75 mm dia G.I "B" pipes fixed in cement concrete 1:2:4. The platforms are to be covered with pyramid shaped FRP roof. The platform is to be with tubular slide & Mini Aquava tunnel Slide made up of high quality FRP the slide is to be fixed at a height of 11ft and runs for a length of not less than twenty ft and the slide should be supported at regular intervals of 6ft using M.S pipes support and the platform ladder with 25mm dia MS pipes with suitable hand rails and steps made out of G.I sheet with tread 4" with powder coated finish, fine quality FRP with suitable design and as per drawing. Moulded FRP slides are non-corrosive, fade free, tough grade, durable hard and should prevent UV light. The work should be executed as per the standard specifications and directions of the engineer in charge with all lead and lift, loading and unloading and any incidental charge required for it	Each	1				1.00		


Sl. No.	Description of work	Unit	No.	Length	Breadth	Depth	Quantity	Rate in Rs.	Amount in
				m	m	m			
	Data Rate	595000					1.00	595000.00	595000
22	Providing fabricating and fixing Multiplay Special slider systems consisting of the plat form with 25mm dia MS pipe and Aluminium chequered plates of size 3x3 ft fitted at 7 ft height from ground level with 4 legs made out of 65mm dia G.I pipes fixed cement concrete 1:2:4. The plat forms is to be fitted with FRP wave slide spiral slide and standard slide with vertical ladder on one side each with GI sheet steps of treads 4" 25mm dia MS pipes with suitable Hand rails fixed at a height of 5 ft and runs for a length of not less than 12 ft the platforms are to be coverd with rramid Shape FRP roof this slide should be supported at regular intervals of 4 ft using MS pipes support powder coated fine quality FRP with suitable design and as per drawing Moulded FRP slides are non-Corrossive fade free ,tough grade ,durable hard and should prevent uv light.The work should be executed as per the standard specifications and directions of the engineer in charge with all lead and lift,loading and unloading and any incidental charges required for the successful competen of the work (ALL FRP items are gel water finish or stoving paint in ovens)								
		Each	1				1.00		
	Data Rate	520000					1.00	520000.00	520000
Total Construction Cost								8754536.	
12% GST								1050544.	
Cost towards DPR & PMC								194000.	
Sub Total								9999080.	
Miscellaneous and rounding off								919.	
Grand Total								10000000.	

Certificate.

- 1 The workspot was inspected and work is found to be necessary.
- 2 The area comes within the Bruhat Bangalore Mahanagara Palike limits.
- 3 The rates adopted based on the PWD SR, Bangalore circle for year 2018-19 and Data rate. -
- 4 The provisions made in the estimate are necessary and essential.



Assistant Engineer,
Yelahanka Project Division


Asst. Exec. Engineer,
Yelahanka Project Division


Executive Engineer,
Yelahanka Project Division

Technical Sanction
Accorded For RS.100.00 lacs
Head of A/C. P.3215
CER NO : 184 Dt: 07.01.2019


TA


CE (YNK)